The National Institutes of Health | Division of Technical Resources | Office of Research Facilities

Design Requirements Manual **News to Use**

November 2026
Vol. 03, No. 11

The formulae $\frac{\partial \rho U_i}{\partial t}+\frac{\partial}{\partial x_j}(\rho U U_j)=-\frac{\partial P}{\partial x_i}+\frac{\partial}{\partial x_j}\left(\mu\frac{\partial U_i}{\partial x_j}\right)+g_i(\rho-\rho_0)$ for building $\frac{\partial}{\partial x_j}(\rho\bar{U}\bar{U}_j)=-\frac{\partial \bar{P}}{\partial x_i}+\frac{\partial}{\partial x_j}\left(\mu\frac{\partial \bar{U}_i}{\partial x_j}-\rho\overline{u_i'u_j'}\right)+g_i(\rho-\rho_0)$ state of the art $\frac{\partial}{\partial x_i}(\rho\bar{U}\bar{H})=\frac{\partial}{\partial x_i}\left(\lambda\frac{\partial \bar{T}}{\partial x_i}-\rho\overline{u_i'h'}\right)$ biomedical research facilities.

Hidden Concrete Risk: Improper Admixture Storage

Out-of-specification (OOS) storage of concrete admixtures is a consequential but difficult-to-detect construction risk. Before batching, admixtures pass through delivery, storage, recirculation, transfer, and dispensing. Exposure to temperatures outside the allowable range, expiration of shelf life, or visible or detectable signs of deterioration, including separation, contamination, discoloration, or changes in odor may leave no distinctive field signature, yet they affect both fresh and hardened concrete performance. An OOS event does not prove concrete nonconformance, but it introduces a deviation from documented materials-control requirements and uncertainty about specified performance at designated test ages and over the structure's service life. That uncertainty can have serious negative effects down the line for concrete serving as a structural material or a finish-system substrate.[1-3]

Admixtures and Concrete Performance

Chemical admixtures are active components of the concrete system which change the performance of the concrete. Admixture dosage is often small, meaning small changes to their performance-altering properties can have an outsized impact on the batch.

- Water-reducing and high-range water-reducing admixtures disperse cementitious particles within the concrete mix, reducing mixing water at a specified workability or increasing flow at a fixed water content. Their effect depends on formulation, dosage, cement chemistry, supplementary cementitious materials, aggregate fines, batching sequence, mixing energy, concrete temperature, and time before discharge. A product or dosage that provides stable flow in one mixture may produce rapid slump loss, delayed setting, excessive fluidity, or air instability in another. Lower water content can improve strength and reduce permeability, but only when the concrete remains cohesive, placeable, and properly consolidated. For a liquid admixture, a change in concentration can deliver both an incorrect chemical dose and an unrecognized change in batch water.[1-3]
- Air-entraining admixtures stabilize microscopic bubbles formed during mixing. Those bubbles improve workability and provide pressure-relief spaces that protect saturated concrete exposed to freezing and thawing. Air entrainment is highly dosage-sensitive and can be affected by cement characteristics, other admixtures, mixing, pumping, and carbon-bearing fly ash, which can adsorb air-entraining agents. The same dosage can produce different air contents and void characteristics as constituent elements or production conditions change. The measured air content of fresh concrete reflects the combined effects of admixture dosage, mixture constituents, and production conditions.[1,2,4]
- Accelerators, retarders, and hydration-control admixtures modify reaction rates. They affect setting, early strength, heat evolution, and time for transport, placement, consolidation, and finishing. Ambient temperature can magnify or offset these effects. Delayed setting can extend vulnerability to bleeding and finishing damage; accelerated setting can shorten consolidation time. Viscosity-modifying and rheology-controlling admixtures increase cohesion or alter flow behavior, improving segregation resistance and pumpability in highly flowable mixtures, but their response depends on fines content, aggregate grading, water content, and compatibility with water reducers. Across all categories, concrete performance depends on admixture condition, chemistry, dosage, constituent compatibility, batching sequence, elapsed time, and placement conditions.[1,2]

OOS Storage Conditions and Potential Consequences

OOS storage or handling falls outside the manufacturer's documented limits for temperature, sunlight exposure, shelf life, agitation, recirculation, cleanliness, or transfer. Excursions include freezing, prolonged heat, separation, dilution, evaporation, and contamination. Disposition is formulation-specific: some products permit controlled thawing and agitation; others require disposal after freezing. Visual uniformity alone does not establish chemical or functional equivalence to qualified product. Likewise, a calibrated dispenser verifies delivered volume, not product condition.[3,5,6,14]

Fresh Concrete Effects

Loss of concentration or homogeneity can act as an unintended underdose, overdose, or fluctuating dose. Possible effects include unexpected slump or slump loss, excessive flow, sticky or harsh rheology, unstable air content, bleeding, segregation, impaired pumpability, incomplete consolidation, and accelerated or delayed setting. These responses may be intermittent. If material has stratified in a storage tank, several loads may appear normal, followed by anomalous loads as a different layer reaches the dispenser. The resulting variability can be misread as ordinary batch-to-batch variation, changing aggregate moisture, or field water adjustment.[1-3]

Substrate and Aesthetic Effects

Changes in rheology, air, bleeding, and setting can alter the finishing window and the response of the surface to screeding, floating, and troweling. Potential consequences include nonuniform texture or color, bugholes, laitance, dusting/chalking, delamination, cracking, and variable surface density. Changes in water demand, consolidation, and pore structure can also influence permeability, drying, and moisture movement. These concerns are significant in biomedical facilities, where slabs commonly receive resinous, resilient, or other moisture-sensitive flooring systems. Concrete can meet structural strength requirements and still be an unsuitable or unpredictable flooring substrate.[7] Flooring acceptance should address the specified moisture and surface requirements; ASTM F2170 measures in situ slab relative humidity, and ASTM F710 addresses preparation for resilient flooring.

'Design Requirements Manual (DRM) News to Use' is a monthly ORF publication featuring salient technical information that should be applied to the design of NIH biomedical research laboratories and animal facilities. NIH Project Officers, A/E's and other consultants to the NIH, who develop intramural, extramural and American Recovery and Reinvestment Act (ARRA) projects will benefit from 'News to Use'. **Please address questions or comments to:** megan.teague@nih.gov

The National Institutes of Health | Division of Technical Resources | Office of Research Facilities

Design Requirements Manual **News to Use**

November 2026
Vol. 03, No. 11



Durability Effects

For concrete exposed to wet freezing and thawing, the presence of entrained air alone does not establish that the air-void structure provides adequate freeze-thaw protection. Routine pressure or volumetric tests measure total air at the time and location sampled, but they do not establish bubble-size distribution, spacing, or stability after pumping, placement, consolidation, and finishing. If an affected air-entraining admixture produces an inadequate hardened air-void system, the concrete may become more susceptible to freeze-thaw damage and deicer scaling. Progressive distress can include surface scaling, spalling, internal cracking, and loss of cover. Where deterioration exposes reinforcement to moisture and chlorides, corrosion can follow, with cracking, delamination, and eventual reinforcement section loss.[8-10]

Structural Effects

An OOS event does not guarantee deficient strength, bond, or structural integrity will result. Structural review becomes appropriate when there is evidence of a relevant affected property, such as reduced in-place strength, abnormal setting that impaired consolidation, cracking, honeycombing, bond impairment, or durability-related deterioration. Depending on the element and failure mode, the engineer, in close consultation with the admixture manufacturer, may need to revisit assumptions supporting reinforcement development length (Ld), concrete contribution to shear (Vc), or concrete-governed anchor limit states. The evaluation should follow the demonstrated material or construction condition; neither an unsupported reduction in structural capacity nor dismissal based on selected passing field tests is justified.[11]

Why Routine Field Quality Control (QC) May Miss an OOS Event

Construction quality-management personnel should review batch tickets and delivery times and observe concrete temperature, consistency, pumpability, discharge, placement, consolidation, finishing, and curing. They may also test slump or spread, air content, density, and prepare specimens for compressive-strength testing. These observations and test results document sampled concrete conditions, help identify batching and placement problems, and help define an affected placement window.[12,13] However, they do not establish the admixture's storage history or identify a specific storage-related cause of an observed anomaly. A ticketed dosage records the reported quantity dispensed, not the condition of the material in the tank. Passing fresh-concrete and strength tests do not establish all aspects of substrate performance or durability, including the protective characteristics of the hardened air-void structure. Sampling may also miss variability affecting particular loads or portions of a placement.[8,9,13]

Conclusion

Field QC is necessary, but cannot replace upstream controls for admixture receipt, traceability, storage, handling, dispensing, and documented disposition of excursions.[3,14] An OOS admixture event alone does not establish nonconforming concrete or justify an assumed structural capacity. It does require a qualified, evidence-based investigation to determine whether concrete properties, substrate performance, durability, or structural assumptions may have been affected. The response should preserve records, define the affected population, and match investigation to the properties plausibly at risk. Disciplined upstream control and documented disposition help prevent a difficult-to-detect materials-handling deviation from becoming a difficult-to-remediate facility-performance problem.

References

1. ACI Committee E701. Chemical Admixtures for Concrete. ACI Education Bulletin E4-22. Farmington Hills, MI: American Concrete Institute, 2022.
2. ACI Committee 212. Report on Chemical Admixtures for Concrete. ACI PRC-212.3-16. Farmington Hills, MI: American Concrete Institute, 2016.
3. ASTM International. Standard Specification for Chemical Admixtures for Concrete. ASTM C494/C494M-24. West Conshohocken, PA: ASTM International, 2024. doi:10.1520/C0494_C0494M-24.
4. Federal Highway Administration. Fly Ash AEA Adsorption Capacity Estimation as Measured by Fluorescence or Foam Index. FHWA-HRT-17-118. McLean, VA: Federal Highway Administration, 2017.
5. Sika Corporation. Sika AEA-14: Air-Entraining Admixture. Product Data Sheet. Accessed September 17, 2026.
6. Sika Corporation. Sika Air-260: Air-Entraining Admixture. Product Data Sheet. Accessed September 17, 2026.
7. ACI Committee 302. Concrete Slabs that Receive Moisture-Sensitive Flooring Materials—Guide. ACI PRC-302.2-22. Farmington Hills, MI: American Concrete Institute, 2023.
8. ASTM International. Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method. ASTM C231/C231M-26. West Conshohocken, PA: ASTM International, 2026. doi:10.1520/C0231_C0231M-26.
9. ASTM International. Standard Test Method for Microscopical Determination of Parameters of the Air-Void System in Hardened Concrete. ASTM C457/C457M-24. West Conshohocken, PA: ASTM International, 2024. doi:10.1520/C0457_C0457M-24.
10. Federal Highway Administration. Guidelines for Detection, Analysis, and Treatment of Materials-Related Distress in Concrete Pavements, Volume II. FHWA-RD-01-164. McLean, VA: Federal Highway Administration, 2002.
11. ACI Committee 318. Building Code for Structural Concrete—Code Requirements and Commentary. ACI CODE-318-25. Farmington Hills, MI: American Concrete Institute, 2025.
12. ASTM International. Standards for sampling and field testing freshly mixed concrete: ASTM C31/C31M, C138/C138M, C143/C143M, C172/C172M, C173/C173M, C231/C231M, and C1064/C1064M.
13. ASTM International. Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens. ASTM C39/C39M-26. West Conshohocken, PA: ASTM International, 2026. doi:10.1520/C0039_C0039M-26.
14. National Ready Mixed Concrete Association. Plant Certification Guidance. Alexandria, VA: NRMCA. Accessed September 17, 2026.

'Design Requirements Manual (DRM) News to Use' is a monthly ORF publication featuring salient technical information that should be applied to the design of NIH biomedical research laboratories and animal facilities. NIH Project Officers, A/E's and other consultants to the NIH, who develop intramural, extramural and American Recovery and Reinvestment Act (ARRA) projects will benefit from 'News to Use'. **Please address questions or comments to:** megan.teague@nih.gov